



NOTES:

1. SIDE SEWERS THAT WILL NOT BE REUSED SHALL BE ABANDONED PERMANENTLY AT THE MAIN AND CAPPED WITH AN APPROVED WATERTIGHT, GASKETED CAP.
2. SIDE SEWERS THAT WILL BE REUSED SHALL BE ABANDONED TEMPORARILY WITH AN APPROVED WATERTIGHT, GASKETED CAP AT THE END OF THE 6" STUB AT THE PROPERTY LINE. INSTALL A 2"x4" MARKER AT THE END OF THE STUB.
3. PAINT PORTION OF SERVICE MARKER THAT IS ABOVE GRADE WITH WHITE PAINT. STENCIL "S/S" WITH 3" TALL BLACK LETTERS.
4. THE DISTRICT WILL DETERMINE IF PERMANENT OR TEMPORARY ABANDONMENT WILL BE REQUIRED. CAPPING REQUIREMENTS TO BE DETERMINED AT THE TIME OF CAPPING PERMIT ISSUANCE. ROW PERMIT MAY BE REQUIRED.